



## Request for Proposal

The Rural Municipality of Rosedale will receive proposals for the project to repair Road 95W between 96N and 97N. The location to be repaired is marked.

Specifications are as follows:

**Part One: from Rd 97 half mile to south: to equalize water between slough on both sides**

- Dig out the collapsed/rotten culvert and replace with new 18-inch diameter by 50ft long (culvert to be provided by the RM of Rosedale)
- 20 yards of pit runs gravels for culvert bed
- 10 yards of traffic gravel around the culvert
- 420 yards of clay to fill and reshape the east slope of the road (4:1 slope); ditch 4 feet from top of road to water
- Two 25 yards loads of traffic gravel supplied by the RM for the top of the road
- 10 yards of small rip-rap, with 5 yards at each end of the culvert.
- Locates including MTS, Gas, Hydro, Cable, Oil, etc. are the contractor's responsibility
- Obtain water license is contractor's responsibility

**Part Two: from Rd 95W south end, just north of 84W**

- 550 feet; 20-foot top; 4:1 slope
- Grade top road back
- 15-inch base gravel, geo
- 1.5-inch and down screen and 3-inch traffic gravel
- Blend back into road going both ways
- **Completion Date: September 30, 2026** unless otherwise agreed to by the Municipality. A penalty may be applied at a rate of \$100/calendar day until the work is complete

All materials and supplies unless otherwise indicated to be supplied by the contractor.

The lowest or any proposal may not necessarily be accepted and the Municipality reserves the right to reject any or all proposals, to waive defects, or to accept and offer which may be considered in the best interests of the Municipality. The Municipality, in its entire discretion may reject or accept all or any part of the proposal or any of the proposals submitted under this proposal call. Completion of work is expected as per tender and quoted amounts. Overages will not be accepted unless approved in writing by the RM of Rosedale to performance of work and/or to additional materials. Notification must be provided to the RM office of the intended commencement date of repairs and expected duration as well as actual commencement date.

**RFP is due by Wednesday, August 5 at 4:00 p.m. They can be mailed, emailed or faxed to the address below. Any questions related to the specifications please contact the municipal office at 204-476-5414.**

Rural Municipality of Rosedale Attention: Mike Davidson  
Box 100 Neepawa, MB R0J 1H0  
Email: [admin@rmrosedale.com](mailto:admin@rmrosedale.com)